



| | |
|------------------|-------------------------|
| ENQUIRY REF. No. | K-E&P/SR/04/2024-25 |
| DATE | 29.04.2024 |
| DUE DATE | 06.05.2024 till 1:00 pm |

Dear Sir,

Please submit your lowest and competitive offer in a SEALED ENVELOPE, DULY SUPERSCRIBING OUR ABOVE ENQUIRY REF. NO., DATE and DUE DATE on it/ OR MAIL, with other details of F.O.R terms, Taxes, Credit period, Delivery offered, Name of the Make, Detailed Specification etc., for the below Supply or Service

| Sl No | Item Code | Item Description | Uom | Qty |
|-------|-----------|---|-----|-----|
| 01 | ---- | EXHAUST FAN FIXING INCLUDING CIVIL WORK AT DPP1 WATER PLANT AS PER BOQ ENCLOSED AS ANNEXURE | No. | 01 |

Please ensure that your offer reaches us on or before Due Date by courier OR Speed post to below office address:

M/s. Karnataka Antibiotics and Pharmaceuticals Limited
Plot No.37, Arka The Business Centre
NTTF Main Road, Peenya Industrial Area
2nd Phase, Bengaluru-5600058
Ph. No.080-23571590

OR you can also mail us to our email: puren@kaplindia.com

NOTE:

1. PLEASE VISIT OUR SITE FOR BETTER UNDERSTANDING THE SCOPE OF WORK AND HAVE AN MOM COPY WITH KAPL TEAM BEFORE SENDING QUOTATION..
2. IF YOU ARE NOT PARTICIPATING IN THE TENDER PLEASE SEND A REGRET LETTER.
3. VENDOR HAS TO QUOTE AS PER OUR TENDER BOQ ONLY IN YOUR COMPANY LETTER HEAD.

Thanking you,

Yours faithfully,
For KARNATAKA ANTIBIOTICS
& PHARMACEUTICALS LIMITED



YUVARAJA. M
DY. MANAGER – PURCHASE DEPT.
MOB: 9945317873


KARNATAKA ANTIBIOTICS AND PHARMACEUTICALS LTD, PEENYA

| Sl No | Description | Unit | Quantity | Rate | Amount |
|---------------------------|---|------|----------|------|--------|
| 1 | Removal of block masonry/concrete/window including cleaning and clearing of debris etc., complete as per specifications & as per directions of Engineer-in-charge. | Lots | 1.00 | | |
| 2 | Construction of 150mm Solid Block Masonry in CM 1:6, the rate should including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge. | Sft | 120.00 | | |
| 3 | Providing 15 mm cement plaster of mix 1:4 (1 cement: 4 fine sand) including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge. | Sft | 240.00 | | |
| 4 | Providing & fixing Turbo Force Exahust Fan including necessary fittings, electrical cabling work etc., complete as per specifications & as per directions of Engineer-in-charge. Size of 600 mm * 600 mm , RPM: 900 , Single Phase ,Number of blades 4 , Air delivary :10520 m ³ / hr, Power consumption : 500 W , Volt : 230 Make: Havells. | Nos | 2.00 | | |
| TOTAL AMOUNT | | | | | |
| GST | | | | | |
| GRAND TOTAL AMOUNT | | | | | |


Note:-

- 1) Before quoting, Contractor has to visit the site to understand the scope of the work
- 2) Contractor should include all supply & labour charges
- 3) Safety norms to be taken care by Contractor only
- 4) Billing will be made on actual measurement at site
- 5) Debris to be shifted outside the factory premises
- 6) Scaffolding to be included in Contractor's scope
- 7) Electrical wall conduit chasing to be included in Contractor's scope


JG(HR)


E(HVNR)


DM(MM)


SM(SRO)