



**KARNATAKA ANTIBIOTICS &
PHARMACEUTICALS LIMITED**

(A Government of India Enterprise)

ENQUIRY REF. No.	K-E&P/SR/0114/2024-25
DATE	03.05.2024
DUE DATE	04.05.2024

Dear Sir,

Please submit your lowest and competitive offer in a SEALED ENVELOPE, DULY SUPERSCRIBING OUR ABOVE ENQUIRY REF. NO., DATE and DUE DATE on it/ OR MAIL, with other details of F.O.R terms, Taxes, Credit period, Delivery offered, Name of the Make, Detailed Specification etc., for the below Supply or Service

SI No	Item Code	Item Description	Uom	Qty
01	----	PATCH FLOOR EPOXY & COVING WORK AT DPP1 PRODUCTION AS PER BOQ ENCLOSED AS ANNEXURE	No.	01

Please ensure that your offer reaches us on or before Due Date by courier OR Speed post to below office address:

*M/s. Karnataka Antibiotics and Pharmaceuticals Limited
Plot No.37, Arka The Business Centre
NTTF Main Road, Peenya Industrial Area
2nd Phase, Bengaluru-560058
Ph. No.080-23571590*

OR you can also mail us to our email: puren@kaplindia.com

NOTE:

1. PLEASE VISIT OUR SITE FOR BETTER UNDERSTANDING THE SCOPE OF WORK AND HAVE AN MOM COPY WITH KAPL TEAM BEFORE SENDING QUOTATION..
2. IF YOU ARE NOT PARTICIPATING IN THE TENDER PLEASE SEND A REGRET LETTER.
3. VENDOR HAS TO QUOTE AS PER OUR TENDER BOQ ONLY IN YOUR COMPANY LETTER HEAD.

Thanking you,

Yours faithfully,
For KARNATAKA ANTIBIOTICS
& PHARMACEUTICALS LIMITED


YUVARAJA. M
DY. MANAGER – PURCHASE DEPT.
MOB: 9945317873

KARNATAKA ANTIBIOTICS & PHARMACEUTICALS LIMITED

BOQ for Epoxy Work - DPP1 production area

SL NO	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	2mm Epoxy Floor				
1	Preparing the surface and eliminating the total dust so as to obtain a sound surface. Creating anchor cuts on the feather ends and applying Epoxy primer and allowing it to set. Laying 2mm thick self leveling Epoxy floor.	Sqm	25		-
	Epoxy Coving				
2	The existing covings shall be levelled with resin topping fine sanded and finished with two coats of Polyurethane Paint/Highsolid Epoxy Coating.	Rmt	20		-
	TOTAL AMOUNT				-
	GST %				
	GRAND TOTAL AMOUNT				

Note:-

- 1) Before quoting, Contractor has to visit the site to understand the scope of the work
- 2) Contractor should include all supply & labour charges
- 3) Safety norms to be taken care by Contractor only
- 4) Billing will be made on actual measurement at site
- 5) Debris to be shifted outside the factory premises
- 6) ESI & Other Statutory requirements to be completed

TE (SHR)

E (BSP)

E (HWNR)